

December 1941

Piggott et al, #1 Beran
C E/2 NE NE 24-17S-12W
Elevation 1849

Cable tool dry hole.

Pennsylvanian conglomerate 3300-3310
3300-3310 Red and green clay shales, not sandy, and
cream limestone, partly mottled red, with
included sand grains.

Arbuckle Residuum 3310-3333

3310-3325 Pink and white silicious clay with abundant
pink, white, and yellow cherts, part oolitic.
3325-3333 Chert, white, pink, yellow, much oolitic.
Some sandy red clay.

Arbuckle Top 3333' Penetration 34' Subsea minus 1484'

3333-3344 Fine buff dolomite with abundant oolitic
chert. Cotter.
3344-3367 T. D. No samples.

The top of the pre-Cotter is estimated at 3355' or minus 1506'
This is probably accurate within ten feet.

RFW