

22-17-13W


WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas

Company - DERBY OIL COMPANY ET AL
Farm - J. Boger No. 6

SEC. 22 T. 17 R. 13W
SE NW SW

Total Depth. 3414'
Comm. 2-18-48 Comp. 3-31-48
Shot or Treated. Acid. w/500 gal.
Contractor.
Issued. 4-17-48

County. Barton
KANSAS



CASING:
8-5/8" 370' Cem. w/210 sx
5-1/2" 3407' Cem. w/100 sx

Elevation. 1929 Ind.

Production. Est. 200 BOPD

Figures indicate Bottom of Formations.

clay, post rock & sand	0-100
shale & shells	275
sand	320
shale & shells	625
red bed & shale	847
anhydrite	875
shale & shells	1230
salt	1450
shale & shells	1550
lime brkn	1730
lime	1840
lime brkn	1965
lime & shale	2135
lime brkn	2230
lime & shale	2425
shale & shells	2535
shale & lime	2680
shale & shells	2880 ?
lime brkn	2850
lime & shale	2870
lime	3020
lime & PT iron	3057
lime	3112
shale	3171
lime & shale	3200
lime	3258
break in K.C. lime	3271
lime	3376
shale	3407
lime RTD	3410
lime	3414
Total Depth	

Tops:
Lansing corr. 3175
r buckle corr. 3407

Cable Tools:
Drilled plug & D.D. 3414 T.D.
fill-up 650' oil 2 hrs.
Swb 13 BOPH/4 hrs.