

21-17-13W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company. BENNETT & ROBERTS OIL OPERATIONS
Farm. Soderstrom No. 1

SEC. 21 T. 17 R. 13W
NW NW SW

Total Depth. 3471'
Comm. 5-27-57 Comp. 6-6-57
Shot or Treated.
Contractor. Bennett & Roberts Drlg. Co.
Issued. 8-10-57

County Barton
KANSAS



CASING:
8 5/8" 322' w/175 sx cem.

Elevation. 1959' DF

Production. Dry

Figures indicate Bottom of Formations.

shale-sand-sand rock	170
red bed-shale-shells	270
shale	545
red bed-shale	395
Anhydrite	925
shale-shells	1400
shale-lime shells	1667
shale-lime	2080
lime	2155
shale	2415
shale-lime	3097
lime	3471
Total Depth	

TOPS: (All Meas. RB)	
Cimmerron Anhydrite	895
Topeka lime	2809
Heebner shale	3121
Toronto lime	3140
Douglas shale	3150
Brown lime	3206
Lansing Kansas City	3218
Conglomerate shale	3433
Arbuckle Dolomite	3451

14' anchor

DST #1 - 3286-3300' Open 60 min.,
weak blow 15 min., strong blow
45 min., rec. 400' gas in pipe,
30' HO & GC watery mud, 60' slight-
ly OC watery mud, BHP in 20 min.,
675 p.s.i., FFP O#, IFP O#.

DST #2 - 3344-76' 32' anchor.
Open 60 min., weak blow 2 min.,
fludhed tool after 30 min., weak
blow 1 min., rec. 5' mud, no
show or odor, BHP in 20 min., 0
p.s.i.

DST #3 3447-71' 24' anchor. Open
60 min., light blow 60 min., rec.
90' very slightly OCM. BHP in 20
min., 900 p.s.i.