

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock,

Wichita, Kansas


15-17-134

Company- LEE PHILLIPS OIL COMPANY
Farm- Oltmanns No. 3

SEC. 15 T. 17 R. 13W
SE NW SW

Total Depth. 3370'
Comm. 12-19-57 Comp. 1-3-58
Shot or Treated.
Contractor. Harms-Burt Drilling
Issued. 3-8-58

County Barton
KANSAS



CASING:
8 5/8" 492' cem w/275 sx
5 1/2" 3367'

Elevation. 1905' KB

Production. 25 BOPD

Figures indicate Bottom of Formations.

shale	150
sand	170
shale	320
sand & shale	390
sand	435
red bed	827
Anhydrite	855
shale	1075
shale & shells	1540
lime & shale	2045
lime	2260
lime & shale	2815
lime	2870
lime & shale	3043
Heebner	3047
lime	3073
Douglas	3082
lime & shale	3140
lime	3364
Arbuckle	3370
Total Depth	

acid on bottom - filled up 120' overnight.
500 gal. acid - swabbed approximately 7
BOPH - no water. Filled up 1150' in 12
hours. p.o.p. at 25 BOPD min.

TOPS:
Anhydrite 827
Heebner 3043
Toronto (Scout) 3062
Douglas (Scout) 3073
Brown Lime 3129
Lansing Kansas City 3141
Arbuckle 3364

DRILL STEM TESTS:

#1 3260-3280 Open 1 hour. Shut in 30"
& 30". Recovered 40' gas, 20' gassy
mud with oil spots. BHP-145#.

#2 3365-3370 Open 1 hour. Shut in 30"
& 30". Recovered 10' heavily oil cut
mud & 15' mud. IBHP-610# FBHP-610#.

Drilled plug to O.T.D. - no show. 22 gal