

✓
WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock,
Wichita, Kansas


16-17-13W

Company- BIRMINGHAM-BARTLETT DRLG. CO.
Farm- Kaiser No. 5

SEC. 16 T. 17 R. 13W
NW NE NE

Total Depth. 3358'
Comm. 12-22-57 Comp. 1-1-58
Shot or Treated.
Contractor. Birmingham-Bartlett Drlg.
Issued. 5-10-58

County Barton
KANSAS



CASING:

8 5/8" 251' cem w/200 sx.
5 1/2" 3351' cem w/125 sx.

Elevation. 1883' DF

Production. 30 BOPD

Figures Indicate Bottom of Formations.

clay & rock	50
shale	251
shale & shells	450
red bed	819
Anhydrite	846
shale & shells	1510
lime & shale	2410
shale & shells	2625
lime & shale	2850
lime	3015
shale & lime	3126
brown lime	3137
lime	3355 RTD
lime	3358 CCTD
Total Depth	

TOPS:

Anhydrite	819
Heebner	3039
Toronto	3059
Brown Lime	3126
Lansing	3137
Arbuckle	3351

DST #1 3349-53, open 30 min., rec. 10' mud.
BHP 0.

Acidized w/500 gal.