

WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY  
 508 E. Murdock Wichita, Kansas

17-17-13 W


Company - BAY PETROLEUM CORPORATION  
 Farm - Harmison No. 1

SEC. 17 T. 17 R. 13W  
 SE SE SW

Total Depth. 3450  
 Comm. 4-14-50 Comp. 5-3-50  
 Shot or Treated.  
 Contractor. John Lindas Oil, Inc.  
 Issued. 5-27-50

County. Barton

KANSAS



CASING:  
 8 5/8" 207' w/125 sx cement  
 5 1/2" 3432 w/75 sx cement

Elevation. 1947 Ind.

Production. Dry

Figures Indicate Bottom of Formations.

soil, rock & gyp	40
shale & shells	165
shale	207
shale & shells	350
sand & shale	460
shale & shells	490
redbed	550
redbed and sand	900
anhydrite	937
shale & shells	1200
shale, salt & shells	1570
shale & shells	1840
lime & shale	1965
broken lime	2070
lime	2155
lime & shale	2255
shale & shells	2385
shale	2610
lime & shale	2705
shale & lime shells	2799
lime, Rotary TD	3441
lime	3450
Total depth	

Tops:

Topeka	2794
Heebner	3106
Brown ls.	3187
Lansing	3201
Conglomerate	3410
Arbuckle	3422

Remarks:

DST 3431-39, open 1 hr, rec. 10' fluid  
 (5' oil & 5' O.C.M.) DP & CO to RTD  
 3439, tested 2 GWPB & 2 GOPH; 500 acid,  
 8 GW & 1 GOPH, DD 11' to 3450' DFTD. Made  
 3 1/20 - 4 BWPB. D&A