

10-17-14W

KANSAS GEOLOGICAL SOCIETY
 KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 508 EAST MURDOCK - WICHITA, KANSAS

COMPANY **ROBINOWITZ OIL**

SEC. 10 T. 17 R. 14W
 LOC. SW SE NW

FARM Riedl

NO. 1

TOTAL DEPTH 3488

COUNTY Barton

COMM. 5-13-66


COMP. 5-20-66

KANSAS

SHOT OR TREATED

CONTRACTOR B & B Drlg.

ISSUED 9-8-66
10



CASING

20	10	
15	8"	@ 270' w/175 SX.
12	6	
13	5 1/2"	@ 3484' w/150 SX.

ELEVATION 1965' KB

PRODUCTION PMP 25 BO PLUS
 25 BWPD (Lans 3206-25)

FIGURES INDICATE BOTTOM OF FORMATIONS

COMPANY: ROBINOWITZ OIL COMPANY
 CONTRACTOR: B & B DRILLING, INC.
 TOTAL DEPTH:
 COMMENCED: May 13, 1966
 COMPLETED: May 20, 1966

TOPS: SCOUT

0	272	Surface Hole
272	610	shale
610	940	shale & shells
940	975	anyh.
975	1650	shale & shells
1650	1865	" " "
1865	2595	lime & shale
2595	3195	lime & shale
3195	3350	lime
3350	3432	lime & shale
3432	3486	lime Total Depth

Topeka	2891
Heebner	3125
Toronto	3138
Douglas	3152
Brown Lime	3196
Lansing	3204
Conglomerate Sd	3429

Set 5 1/2" csg. @ 3484' W/ 150 sacks cement.

We certify the above and foregoing to be a true and correct copy of the log on the #1 Riedl, located in Barton County, Kansas.

B & B DRILLING, INC.

Bill Selzer President

Subscribed and sworn to before me this 21st day of May, 1966.

Twister Madris Coleman
 Notary Public

January 12, 1970