

10-17-14W


WELL LOG BUREAU-- KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - THE PHIL-HAN OIL COMPANY
Farm - Riodol No. 1

SEC. 10 T. 17 R. 14W
SEc SW

Total Depth. 3495' PB 3350'
Comm. 7-6-47 Comp. 7-18-47
Shot or Treated. Shot
Contractor.
Issued. 8-30-47

County. Barton
KANSAS



Elevation. 1962 act. 1947

Production. Dry

CASING:

8-5/8" 596' Com. w/275 sx
5-1/2" 3351' Com. w/ 75 sx

Figures Indicate Bottom of Formations.

shale, shells & sand	25
shale & shells	195
shale	485
sand	565
red rock	945
anhydrite	975
shale & shells	1030
shale, shells & salt	1480
shale & shells	1680
lime	1820
shale & lime	1915
lime	2300
lime & shale	2450
shale & shells	2650
lime & shale	2755
lime	3155
lime & shale	3185
lime	3420
lime & conglomerate	3440
conglomerate	3471
Arbuckle lime	3495
Total Depth	

Plugged back to 3350'

Tops:

Kansas City	3187
Conglomerate	3421
Arbuckle	3474

Perf. 63 shots 3200-21'.
Tested w/swab 16 hrs - $\frac{1}{2}$ BWFH,
no oil.
Perf. 15 shots 3285-3290'.
Tested w/swab 10 hrs. - HFW, no
show oil.