

December, 1945

Continental, 2# 1 Bahr
Sec. 32-17s-14w, SE SW SE
Elev. 1973'

Rotary

Pennsylvanian conglomerate

3459-3479 Sandy limestone at the top; rare pink, yellow,
and white flinty cherts below; some dull
white cherts near 3475'. Rotary samples
too poor to subdivide section, but marine
conglomerate at the top with probably residuum
at the base.

Arbuckle Top 3479' Penetration 13'

Subsea -1506'

3479-3492 White coarsely crystalline dolomite. Pre Cotter,
POST BOYCE member.

Remarks: Dry hole.

Restored top of the Pre-Cotter cannot be estimated
but is above -1500'.

RFW