

Dec. 1945

Phillips # 1 Frieb
Sec. 33-17s-14w, SE SW
Elev. 1959'

Rotary

Pennsylvanian conglomerate

3418-3432 Rare oxidized cherts in rotary samples.

Residuum of Arbuckle Top 3432' Subsea-1473'

3432-3439 Fresh translucent cherts with red clay
contacts. Poorly shown in rotary samples.

Arbuckle Top 3439' Penetration 12' Subsea -1480'

3439-3440 Reported as cherty COTTER dolomite by
Price, Letter # 52, 1943. No dolomite
present in $\frac{1}{2}$ hr. circulation sample at
3440', deepest sample available.

3440-3451 No samples. Interval 3441-3451 cored.

Remarks: Test made 45 BBLS OIL and No water from the
Arbuckle. PB to the Lansing where it made
24 BBLS OIL and 18 BBLS WATER.

RFW