

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas


14-17-15W

Company: Republic Natural Gas Co.,  
Farm: F, W. Axman No. 1

SEC. 17 T. 17 R. 15W  
SW NE SW

Total Depth. 3500'  
Comm. 9-7-57 Comp. 9-19-57  
Shot or Treated.  
Contractor. Gabbert-Jones Drlg.,  
Issued. 11-9-57

County Barton KANSAS



Elevation. 1913 R. B.

Production. Dry

CASING:

8 5/8" @ 935' W/350 sks. cem.  
5 1/2" @ 3499' W/100 sks. cem.

Figures indicate Bottom of Formations.

surface clay	35
Post rock	45
shale	170
shale & shells	370
Dakota sand	450
shale & shells	520
red bed & Iron	640
red bed & shale	710
red bed, shale & shells	840
red bed	930
Anhydrite	965
red bed, shale & shells	1015
shale & shells	1700
lime	1845
lime & shale	2125
shale & shells	2210
shale & lime	3120
lime	3432
Conglomerate	3443
Arbuckle Dolomite	3500
Total Depth	3500

Scout Tops:

Anhydrite	930
Topeka	2806
Heebner	3128
Toronto	3142
Douglas	3157
Lansing	3191
Conglomerate	3432
Arbuckle	3441