


\*

State Ks. Field W.C.  
 Company MUSGROVE County WICHITA  
 Farm NELSON No. 1  
 Sec. 16 Twp. 17 Range 37

Spot C NW NW  
 Contractor MUSGROVE  
 Remarks 5200'



Comm. 7-3-57 <sup>350'</sup> Comp. 12-18-57  
 Elev. DF 3359 GL <sup>350'</sup> KB 3362 TD 5962 PB 4617  
 Pay MARM 4528-32

I.P. ST. TST. PUMP. & BOP Press. GRAN. 26.3  
 Casing Record: 13 3/8 ..... 7"  
 20" ..... 10 3/4 ..... 5 1/2"  
 16" ..... 8 5/8 549 / 275 4 1/2 4607 / 240

	Sample	Log
<del>φ 3530</del>	ANHY 2525	Wab 3540
JUL 17 DST 4504-45	FT R. 2967	TOP 3797
op 1 hr. work below	Wab 3624	Heeb 4007
rec. 115' OCM	MARM 4463	TOR 4021
FP 0-120 BHP 1120/200	Cher 4660	LANS-750 4097
<del>φ 4922</del>		MARM-1115 4477
JUL 24 <sup>TTD</sup> 5155 DBA (FOR MUSGROVE)		CHER-1175 4632
ran log.		MoR-1475 4831
PEPL TO DRILL IT ON	-1501	" sd 4860
TO ARBUCKLE <del>φ 5540</del>		76
JUL 31 RTD 5962	-1571	ST. GEN. 4930
condition hole for		VIOLA 5485
to TST or φ deeper.	X -2309	ARBUC 5668
AUG 7 LC 5985 RTD 6000' ran log		<del>SPUR 5960</del>
running cig (TO MARM)		REASON 5960
AUG 14 pipe stuck @ 1080 cut off and		
washing over		
AUG 28 re-conditioning hole recovered		
PB 4740 4 1/2" O	RECT pf 16/4528-32	
bailed 20 3/4 gal fluid (55% oil)		
in 1 hr. A/500 M	swabbing &	
testing.		
SEP 4 set @ 4518 59/250 pf 18/4503-09		
N.S. A/500 (MA) swab 18 BSWPH	SPK @ 4480	
3Q/250 φ PL φ cement		

SEP 11 CG 4617 16/45 28-32 MA/1000  
swab 1 BOPH swab 1 1/4 BOPH for  
72 hrs. running T & rods

SEP 18 POP WOT

SEP 25 L OCT 2 ✓ OCT 9 ✓ OCT 16 A/1000  
rec. load Pump 12 BO in 9 hr.

OCT 23 WOT

OCT 30 A/2000 swab 3/4 rot BOPH  
Treated 1000 gal lease oil pumped  
12.57 BO in 24 hrs. pumping.

NOV 6 ✓

NOV 13 pump 6 BO in 9 hr. prep to treat  
NOV 20 FR/3000 SD/2000 swab load

NOV 27 ↓ POP pump 19 BO in 9 hr.  
pump 28 B fluid (50% oil) in 19 hr

DEC 4 Pump 26 BO in 12 hrs fst.

DEC 11 pump 7 TOF BO in 12 hrs SI

DEC 18 ST POT. pump 8 BOPD

GRAV. 26.3

