


11-177W Map No. _____
OPER CIMARRON EXPL. INC. & CLEARY PETR.
Liberal, Ks.
WELL #3 SEE
Wakefield Drlg.
FIELD Brookover (Lans Oil)
I.P. _____



S-T-R 19-17S-31W
SPOT C SE NE
CO SCOTT (Ks)
ELEV 2959 KB
(Log)
Anh 2250 $\neq$ 709
B/Anh 2314 $\neq$ 645
Hb 3895 - 936
Lan 3932 - 973
"B" 3970 - 1011
"C" 3985 - 1026
"D" 4020 - 1061
"D-1" 4034 - 1075
"E" 4051 - 1092
"F" 4116 - 1157
"G" 4122 - 1163
"H" 4157 - 1198
"I" 4184 - 1225
"J" 4215 - 1256
LTD 4225 - 1266
RTD 4225 - 1266

- DST #1 (Lans) 3964-82, Op 30", WB/30", R 5' M, ISIP. 1008#/
30", FP's 0-41#, FSIP 967#/30"
DST #2 (Lans) 4015-28, Op 90", R 5' Oil & 70' HMCO & 100'
HOCM, ISIP 832#/30", FP's 0-62#, FSIP 790#/30"
DST #3 (Lans) 4134-80, Op 1 hr, GB/1 hr, R 275' SW, ISIP
1040#/30", FP's 21-228#, FSIP 1019#/30"
DST #4 (Lans) 4185-92 (Str Pkr), Op 1 hr, R 235' Mdy SW,
ISIP 1082#/30", FP's 21-187#, FSIP 1065#/30"
RTD 4225, Wellex Log, 5 $\frac{1}{2}$ " @4093 w/100 sx.
Pf 16/4021-26 (Lans), 500 MA, § 1d
§ 30 BWPH w/SSO/3 hrs, Sq 4021-26 w/150 Sx., 4/4013 $\frac{1}{2}$ -14 $\frac{1}{2}$
(Lans) 250 MA, § 1d, § 36 BSW PH, 3 hrs, D & A 11-14-65
COMPLETED

Note: Cimarron Expl., Inc. took over well at casing point
Was Cleary Petroleum, Inc.

Data Inc

MISC DATA

GE. Bill Atkinson ELEV 2956 DF SPUD DATE 10-16-65
FTG _____ 2951 GR DRLG COMP _____
SUPPT _____ FR by DATA 10-14-65
CSG 8" @296 w/275 sx. 5 $\frac{1}{2}$ " @4093 w/100 sx. COMP by " 10-18-65