

0-106W

MAP NO.

SEC. 19-17S-31W

STATE Kansas COUNTY Scott

LOC C NE NE

PER Cleary Petroleum, Inc. - Oklahoma City, Okla.

FT/FR LINE

#1 FARM See

FT/FR LINE

Brookover

ELEV 2948 GR 2954 DF 2956 KB

E. F. Wakefield, tools

GEOL. Bill Atkinson

4100' Test

R 8-25-64

SPUD

8-27-64

COMP. 10-13-64

D 4035

FM.

Lans

PBTD


PRODUCING FAL FROM TO PER W/HOLES TREATMENT

Lans 4019 (only)

3

250A

Co Pump: 63 BOPD / 66 BWPD (Gr 32.4 deg)

Casing
Record

Data Inc.

8-5/8" @ 292' w/225 Sx. 4½" @4035' w/100 Sx.

(KB Log Tops:)

Cimm Anh	2254 / 702		Tor	3910 - 954
B/Cimm Anh	2310 / 646		Lans	3934 - 978
Hb	3894 - 938		LTD	4035 - 1079

DST #1 (Lans) 3962-89, Op 1½ hrs, R 1050' Mdy SW w/show oil, ISIP 877#/30", IFP 88#, FFP 460#, FSIP 932#/30"

DST #2 (Lans) 4013-25, Op 1½ hrs, R 340' oil & 280' OCM & 240' OCSW, ISIP not taken, ISP 44#, FFP 230#, FSIP 296#/30"

DST #3 (Lans) 4030-35, Op 1½ hrs, R 620' OCSW, ISIP not taken, IFP 104#, FFP 195#, FSIP 320#/30", RTD 4035, Sj Log, 4½" @4035 w/100 Sx. Perf 3/4019 (Lans), \$ dry/7 hrs, \$ sli show oil, 250A (15%), \$ 1d, \$ 41 BO & 60 BSW/24 hrs, POP, P 124 BO & 20% wtr/24 hrs, P 70 & 20% wtr/24 hrs, Co P 63½ BOPD & 66 BWPD, Gr 32.4 deg., Lansing 4019 - COMPLETED 10-5-64