


State Kansas Field
 Company Imperial County Scott
 Farm See No. 1
 Sec. 19 Twp. 17S Range 31W
 Spot SW NE NW
 Contractor
 Remarks
 Comm. Comp. 1-12-53
 Elev. DF2966 GL KB TD 4685 PB 4430
 Pay DRY & ABANDONED



I.P. Press.
 Casing Record: 13 3/8 7"
 20" 10 3/4 5 1/2" 4685/cem.
 16" 8 5/8

	Sample	Log
DST 2744-70, op 1/4 hr, rec 10' M; DST 3833-63, op 1 hr, rec 150' XW; DST 3878-3903, op 1 hr, rec 558' XW; DST 3968-80, op 1 hr, rec 60' HO&GCM.; DST 3986-95, op 1 1/2 hrs, rec 1490' XW; DST 4017-35, op 1 hr, rec 125' O&GCM; DST 4126-44, op 1 hr, rec 25' OCM; DST 4173-81, op 1 hr, rec 30' M; DST 4192-4201, op 1 hr, rec 200' M&W + 500' sulfW; DST 4221-25, op 1 hr, rec 30' M; DST 4228-70, op 3/4 hr, rec 189' XW + 2151' SulfW; DST 4362-85, op 3/4 hr, rec 10' M; DST 4384-4433, op 3/4 hr, rec 365' gas + 30' HOCM + 100' oil & muddy GCO; DST 4473-85, op 1 hr, rec 10' M; DST 4525-53, op 3/4 hr, rec 10' M; DST 4566-74, op 1 hr, rec 8' M; perf 16/4618-23, NS; A/500, No sho; perf 50/4402-12, NS, A/500, fls 16 Bo	Heeb 3852 Lans 3875 Marm 4321 Miss 4584	Lans 3900 B/KC 4322 Miss 4584

10 hrs; (no wtr); A/5000, swb 21 BO/10 hrs;
perf 16/4298-4301, 16/4316-20, A/500, swb 2
BWPH w/SSO, PB 4200, perf 16/4176-80, A/250, swb
8 BWPH, PB 4045, perf 16/4027-62, A/500, swb
30 BWPH, perf 8/3971-73; sqz; CO 3982, perf

14/3974-77, NS; A/500, swb 60 BWPH; sqz all except
4402-12; CO 4430, pump 3/4 BOPH + 3% wtr; swb 13
BO/15 hrs; 26 BO/24 hrs + 2% wtr; later swb 3
BOPD:

D & A.