

PINTAIL PETROLEUM, LTD.

412 EAST DOUGLAS, SUITE ONE
WICHITA, KANSAS 67202
(316) 263-2243

JUN 4 1993

COMPLETION REPORT

Dickman 'A' #2
C NE NE, Sec. 17-17S-24W
Ness County, Kansas

%%%

05-28-93 Move in completion rig. Drill out cement.

06-01-93 2200' of oil in hole since Saturday noon. Appx .85/hr fill-up. Swab hole down. Trace of water on bottom. Swab .85 bbl/hr. Acidize w/750 gallons 15%. Treat very tight. 1/4 bbls slow increase to 1 bbl/minute at 800#. Vacuum in 4 minutes. Swab well down w/103 bbls out of 126 bbl load, our first oil show. Swabbing at 4:30pm 1200' off bottom, 25+ /hr nearly all oil. Will check fill-up and put on production as soon as possible.

6/3/93 Fill-up this morning
3300 ft. oil 3 ft. water

PINTAIL PETROLEUM LTD
WICHITA KS 67202

17-17 -24W
C NE NE

#A-2 DICKMAN

site: 4 S & 2-1/2 E OF ARNOLD KS		city: NESS		API 15-135-23753	
contr: MALLARD JV #1		field: DICKMAN			
geol: INNES PHILLIPS					
fr date 05/07/93	spd date 05/14/93	drig comp 05/21/93	card issued 07/19/93	last revised 07/19/93	
ELV: 2456 KB, 2451 GL LOG		IP status:			
tops.....depth/datum		OIL, P 35 BO & 5 BWPD, MISS 4418-4426 ,			
ANH.....1742 +714		CSG: 8-5/8" 219.56 / 125 SX (ALT 2), 5-1/2" 4418 / 300			
B/ANH.....1772 +684		SX			
HEEB.....3780 -1324		NO CORES			
LANS.....3822 -1366		DST (1) 4340-4426 (CHER, MISS), / 30-45-90-60, REC			
BKC.....4112 -1656		120' OIL, 200' MDY GSY OIL (55% OIL, 35% M, 10% G)			
PAW.....4238 -1782		ISIP 1250# FSIP 1234# IFP 50# -98# FFP 128# -197#			
FT SC.....4318 -1862		IHP 2148# FHP 2090# BHT 124 °			
CHER SH.....4344 -1888		TRGT ZN: MISS, PTD 4400 (MISS), MICT - CO, (MISS			
MISS.....4419 -1963		OH), AC 250 GAL (MA) & 500 GAL (15% FE), SWB DWN,			
RTD.....4426 -1970		SO, SET 2-3/8" TBG AT 4375, NO PKR, POP, P 35 BO & 5			
		BWPD (GR 36), 6/2/93			