

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-62-3-117

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

API NUMBER N/A

LEASE NAME Elmore

WELL NUMBER #1

1980 Ft. from S Section Line

1980 Ft. from W Section Line

SEC. 17 TWP. 17S RGE. 24W (E) or (W)

COUNTY Ness

Date Well Completed 2-21-63

Plugging Commenced 10-31-02

Plugging Completed 10-31-02

LEASE OPERATOR GRAND MESA OPERATING COMPANY

ADDRESS 200 E. First St., Ste 307 Wichita KS 67202

PHONE# (316) 265-3000 OPERATORS LICENSE NO. 9855

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10-28-02 (date)

by Oliva E. Raigosa (XCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached?

Producing Formation Mississippian Depth to Top 4385 Bottom 4395 T.O. 4395

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
	Surface			8 5/8	115	None
	Production			5 1/2	4390	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set.
In cased hole: Pumped 40 SX cement (60/40 Poz, w/6% Gel and 300# Hulls) on bottom, then mix 19 SXS Bentonite Gel up to approximately 1750, then pump 135 SXS cement (60/40 poz w/6% Gel) to surface, then pump 50 SXS Cement down Braden Head -- Job Complete.

Name of Plugging Contractor Swift Services, Inc. License No. 38382

Address P O Box 466 Ness City, KS 67560

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: GRAND MESA OPERATING COMPANY

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

Ronald N. Sinclair, President (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Ronald N. Sinclair

RONALD N. SINCLAIR President

(Address) 200 E. First St., Ste 307, Wichita KS 67202

SUBSCRIBED AND SWORN TO before me this 14th day of November, 2002
Phyllis E. Brewer
Notary Public - State of Kansas
My Appt. Expires 7-21-03
My Commission Expires

PHYLIS E. BREWER Notary Public

July 21, 2003