

**GRAND  
MESA****OPERATING COMPANY**(316) 265-3000  
FAX: (316) 265-3455307 FARMERS AND BANKERS BUILDING  
200 EAST FIRST STREET  
WICHITA, KANSAS 67202

WELL NAME: Kilmore #3

OPERATOR: Grand Mesa Operating Co.

LOCATION: C/SW/SW Sec. 17-17S-24W

CONTRACTOR: Duke Drilling

CNTY/STATE: Ness County, Kansas

FIELD NAME: Dickman

SURFACE: 8 5/8" @ 360'

GL: 2413' KB: 2422'

API: #15-135-23755

06-01-93 MIRU  
Spud @ 2:10 p.m.  
Plug down @ 8:00 p.m.  
Ran 8 jts 8 5/8" 23# @ 360';  
Cement 200 SX 60/40 Pozmix, 3% C.C.; 2% Gel;  
Survey 1/4 @ 366';

06-02-93 Drilling at 765';

06-03-93 Drilling at 2345';

06-04-93 Drilling at 2955';  
Survey 1 @ 2609';  
Survey 1/2 @ 3138';

06-05-93 Drilling at 3640';

06-06-93 Drilling at 4188';  
Survey 3/4 @ 4300; Pipe strap @ 4300' .50 long to board  
  
DST #1 (4261'-4300') (30-30-30-30)  
1st open: wk blow died in 8 min.  
2nd open: no blow  
Rec: 10' mud; No show  
  
IFP 19-19 ISIP 19-19 FSIP 19-19

06-07-93 Drilling @ 4349';

06-08-93 TD 4460'; Logged to 4464;  
Plugged with:  
  
50 SX @ 1740'  
80 SX @ 1150'  
40 SX @ 600'  
40 SX @ 360'  
10 SX @ 40'  
15 SX Rat hole  
  
Plug down @ 7:00 a.m. 6/8/93;

Dry &amp; Abandoned

**FINAL REPORT**