

Company Palomino Petroleum
Lease Tilley #2
Date March 13, 1997
Contractor Express Well Service
Type Job; Rod Part - 6th rod - 7/8"
body break, had tubing tested - found 2 blowouts, changed
pump

DOWN HOLE EQUIPMENT RECORD

Polish Rod 1 1/4" x 22'
Liner 1 1/2" x 10'
Rod Subs 8' x 7/8"
Rods 85 x 7/8", 10 x 1" on bottom & 77 x 3/4" (4300')
Pump Description;
Insert _____
Tubing 2 1/2" x 2 1/4" x 12' x 15' x 17' w/ 2 1/4" x 4'
metal plgr. 1' x 1" gas anchor
Casing Size 5 1/2"
Tubing Subs 2', 4', 6', 10'
Tubing;
Size & Thread 2 7/8" EUE 8 rd. & tailpipe
No. of Joints 143 & 1
Mud Anchor 2 7/8" x 5 1/2" TAC

Directions to Lease; _____

