

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-62-34117

API NUMBER 15-135-20,711

LEASE NAME Humphrey

WELL NUMBER 1

660 Ft. from S Section Line

660 Ft. from E Section Line

SEC. 18 TWP. 17S RGE. 24 (E) or (W)

COUNTY Ness

Date Well Completed _____

Plugging Commenced 07-13-95

Plugging Completed 07-14-95

JUL 20 1995

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Grand Mesa Operating Company

ADDRESS 200 E. First Street, Suite 307 Wichita, KS. 67202

PHONE (316) 265-3000 OPERATORS LICENSE NO. 9855

Character of Well D&A

Oil, Gas, D&A, SWD, Input, Water Supply Well

The plugging proposal was approved on 07-13-95 (date)

by Richard Lacey (KCC District Agent's Name).

Is ACD-1 filled? Yes If not, is well log attached? _____

Introducing Formation Mississippi Depth to Top 4376 Bottom 4403 T.C. 4403

How depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
	Surface			8 5/8"	261	0
	Production			5 1/2"	4376	1323

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug are used, state the character of same and depth placed, from feet to feet each set. Bottom plug: sanded off to 4326' 5 sks of cement. Loaded hole. Added mixed 80 sks of cement, displaced it down with gel 8 sks. Mixed 50 sks at 660. 50 sks at 290'. Topped off well with 45 sks of cement. Max. Pressure 600 lbs.

Name of Plugging Contractor D.S. & W. Well Servicing, Inc. License No. 6901

Address P.O. Box 231, Claflin, Kansas 67525

Name of Party Responsible for Plugging Fees: Grand Mesa Operating Company

State of Kansas COUNTY OF Barton, ss.

Arthur P. Strube (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.

(Signature) Arthur P. Strube

(Address) P.O. Box 231, Claflin, Kansas 67525

SUBSCRIBED AND SWORN TO before me this 18th day of July, 19 95

Karlynn K. Beck
Notary Public

My Commission Expires: 09-28-98

USE ONLY ONE SIDE OF EACH FORM



Form 67-4
Revised 05-88

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev.03/92

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-135-20,711 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Grand Mesa Operating Company KCC LICENSE # 9855
(owner/company name) (operator's)
ADDRESS 200 E. First St., Suite 307 CITY Wichita

STATE Kansas ZIP CODE 67202 CONTACT PHONE # (316) 265-3000

LEASE Humphrey WELL# 1 SEC. 18 T. 17S R. 24 (East/West)

- C - NE - SE SPOT LOCATION/QQQQ COUNTY Ness

660 FEET (in exact footage) FROM S (N) (circle one) LINE OF SECTION (NOT Lease Line)

660 FEET (in exact footage) FROM (E)W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL ☐ GAS WELL ☐ D&A ☒ SWD/ENHR WELL ☐ DOCKET#

CONDUCTOR CASING SIZE SET AT CEMENTED WITH SACKS

SURFACE CASING SIZE 8 5/8" SET AT 261 CEMENTED WITH 150 SX Common, 3% CC SACKS
2% Gel

PRODUCTION CASING SIZE 5 1/2" SET AT 4376.76 CEMENTED WITH 100 SX Pozmix 60/40 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: Open hole Completion

ELEVATION 2428/2433 T.D. 4403 PSTD ANHYDRITE DEPTH 1701-31
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD ☒ POOR ☐ CASING LEAK ☐ JUNK IN HOLE ☐

PROPOSED METHOD OF PLUGGING Multiple Cement Plugs

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? No IS ACO-1 FILED? yes

If not explain why?

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Donald Froelich PHONE# 913) 731-2572

ADDRESS Box 10, RR #1 City/State Arnold, KS 67515

PLUGGING CONTRACTOR D S & W Well Service KCC LICENSE # 6901

ADDRESS P O Box 231, Claflin, KS 67525 (company name) (contractor's)
PHONE # (316) 587-3361

PROPOSED DATE AND HOUR OF PLUGGING (if known?)

PAYMENT OF THE PLUGGING FEE (K.A.R. 32-3-113) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 6-27-95 AUTHORIZED OPERATOR/AGENT: Ronald N. Sinclair
(signature)

RONALD N. SINCLAIR, President