

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
 412 Union National Bk. Bldg., Wichita, Kansas


34-17-25W

Company - MAGNOLIA PETRO. CO.
 Farm - Reed "E" No. 2.

SEC. 34 T. 17 R. 25 W
 SE NW NW

Total Depth. 4342 DF SIM
 Comm. 4-27-45 Comp. 6-11-45
 Shot or Treated.
 Contractor.
 Issued. 7-21-45

County. Ness
 KANSAS



CASING:
 8 5/8" 250' LI
 5 1/2" 4334' LI
 2 1/2" 4340' LI

Elevation. _____

Production. Pot. 25 B

Figures Indicate Bottom of Formations.

sand & shale	249
shale, shells, sand	880
shale & shells	1020
anhydrite	1065
shale & shells	1660
anhydrite	1675
shale & shells	2140
salt & shale	2325
shale & shells	2440
shale & lime	2645
lime	3045
shale	3085
shale & lime	3125
shale	3205
lime & shale	3330
shale	3510
lime	3743
chert	3767
Lansing- K.C.	4315
conglomerate sand	4334
Mississippian	4336
dolomite	4342
Total Depth DF SIM	

Tops:

Chert	3743
Lansing-K.C.	3767
Conglomerate	4315
Mississippian	4336 DF
Dolomite	4336

Cored 4338 - 42' rec.
 First 18" Fair sat.
 Next 18" Good sat.

Standardized
 Drilled plug & c/o to
 4342. no oil or wtr.
 Acidized after being perf.