

SHEARER

B-2

1

BARNETT OIL COMPANY

KANSAS

LEASE

WELL NO.

TEST NO.

COMPANY

DISTRICT

 LOCATION
 26
 23-17-25

FIELD

COUNTY
NessSTATE
KansasCONTRACTOR
Barnett Drilling Co.

MUD DATA

Kind
StarchWeight
10.3 lbs.-gal.Viscosity
12 Sec.Filter Loss
8.8 c. c. Filter Cake 2/32 in.Est. Gauge
Depth Temp. 110 F.Time Tool Open
1 HourTime Closed In.
30 MinutesDepth
BT. Gauge 4439' Blanked OffBT.
P.R.D. No. 207 No

12 Hr. Clock No. 1736

Pressure
Readings Field Office CorrectedInitial Hydro
Mud Pressure 2416 p.s.i.

Initial Flow Pres. 17 p.s.i.

Final Flow Pres. 32 p.s.i.

Closed in Pres. 1121 p.s.i.

Final Hydro
Mud Pressure 2369 p.s.i.

OIL WELL CEMENTING CO.

HOLE AND TOOL DATA

Total Depth	4464'	Casing Perforations	Top - Bottom -
Top Packer Depth	4456'	Bottom Packer Depth	-
Casing or Hole Size	7 7/8"	Linert or Rathole Size	-
Formation Tested	Mississippi		
Size Drill Pipe	4 1/2" API FH	Size Drill Collars	-
Size Bottom Choke	1"	Size Surface Choke	5/8"
Size Hook Wall Packer	-	Size Rings	-
Size D. E. Wall Packer	6 3/4" ESA	No. Packers	1
Size & Length Anchor	5" X 8'		
PRD Device No.	1942	Depth	4464'
		Blanked Off	Yes

REMARKS: Tool opened with a weak blow that decreased

throughout the test & died.

Recovered 60' of gas & 60' of slightly oil

cut mud.

Amount of Cushion
None


All depths measured from

Kelly Bushing

No. Folders
Reproduced

5

TIME



PRESSURE

Each Horizontal Line Equal to 1000 p.s.i.