

26-17-25W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- MAGNOLIA PETROLEUM
Farm- Ross Potter No. 4

SEC. 26 T. 17 R. 25W
C W/2 SE NE

Total Depth. 4425'
Comm. 6-9-59 Comp. 6-28-59
Shot or Treated.
Contractor. Barnett Drlg.
Issued. 10-24-59

County Ness
KANSAS



CASING:
8 5/8" 250' cem w/150 sx.
5 1/2" 4424' cem w/425 sx.

Elevation. 2468'

Production. 195 BOPD, NW

Figures Indicate Bottom of Formations.

shale & shells	250
shale & red bed	1720
lime, shale & shells	2590
shale & lime	3785
lime	4258
lime & shale	4386
lime	4425
Total Depth	

TOPS:
Lansing 3797
Ft. Scott 4295
Mississippi 4387

PERFORATIONS:
#1 Perf. 4390-4396 w/24 shots
#2 Perf. 4402-4408 w/24 shots