


JUN 1 1973

DRILLERS LOG



#1 Rupp "A" per kcc comments

CASING RECORD: 238.68' of new 8-5/8" surface casing. COMPANY: Patrick Petroleum Corporation DESCRIPTION: C NW SW Section 10-17S-25W Ness County, Kansas
CONTRACTOR: Strata Drilling, Inc.
TOTAL DEPTH: 4439' COMMENCED: December 4, 1972 ELEVATION: 2473' KB
COMPLETED: December 17, 1972

FORMATION	FROM	TO	REMARKS
Shale, Sand & Rock	0	277	Ran 238.68' of new 8-5/8" surface casing; set and cemented at 244.68' with 150 sacks of common cement, 2% gel and 3% C. C. Plug down at 10:30 A. M. December 5, 1972.
Shale	277	290	
Shale, Red Bed, Sand Streaks	290	963	
Shale & Sand Streaks	963	1199	
Anhydrite	1199	1207	
Shale & Red Bed	1207	1272	
Sand	1272	1522	
Shale & Shells	1522	1590	
Shale	1590	1760	
Lime & Shale	1760	1809	
Anhydrite	1809	1841	
Sand Streaks, Shale & Lime	1841	2105	
Shale w/Lime Streaks	2105	2360	
Lime & Shale	2360	4439	

ROTARY TOTAL DEPTH: 4439'

RECEIVED
STATE CORPORATION COMMISSION
DEC 27 1972
CONSERVATION DIVISION
Wichita, Kansas

Log Tops	Depth
Sc	1809
Heeb	3803
Tor	3822
Lans	3842
Bkc	4141
Marm	4188
Pawn	4272
Ft Sc	4343
Cher	4369
Miss Dol	4428

5 1/2" casing set and cemented at 4429' with 125 sacks of pozmix, salt saturated. Plug down at 12:05 A. M. December 17, 1972.

Ltd & Rtd 4444

K. G. S. LIBRARY

STATE OF KANSAS)
) ss.
COUNTY OF BARTON)

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING, INC.

Charles W. Steincamp
Charles W. Steincamp, President

Subscribed and sworn to before me this 20th day of December, 1972.

My Commission Expires:

December 14, 1973

Elaine H. Taylor
Elaine H. Taylor, Notary Public

