

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas


Company- HUGOTON PRODUCTION CO.
Farm- Floyd No. 2

SEC. 19 T. 17 R. 29W
C E/2 NW SW

Total Depth. 4430
Comm. 11-21-52 Comp. 1-9-53
Shot or Treated.
Contractor. Glenn R. Nye Drilling Co.
Issued. 2-28-53

County Lane

KANSAS



Elevation. 2835.5 KB

2836.009
Production. 75 BO, 20% water

CASING:

8 5/8 242' w/ 250 sx cement
5 1/2 4427' w/ 50 sx cement

Figures indicate Bottom of Formations.

surface sand & clay	40
sand	200
shale	1000
sand & shale	1150
shale	1250
red bed, shale & sand	1610
shale & shells	1678
anhydrite	1705
red bed & shale	2230
shale, salt & anhydrite	2390
shale	2510
shale & red bed	2570
lime & shale	4085
lime	4135
lime & shale	4430
Total Depth	

TOPS:

Anhydrite	2228
Heebner	3921
Lansing KC	3956

DST #1: 4316-45 open 1 hr. rec. 2'
drilling mud BHP 0#

DST #2: 4401-30 open 1 hr. rec. 100'
O & G C mud 120' oil 1020' gas
BHP 1120#

DST #3: 4396-4422 open 1 hr. rec. 30'
heavy OC mud BHP 290#

core no. 1	4315-4345
core no. 2	4400-4430