

17-17-31W ✓


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- D. R. LAUCK OIL COMPANY, INC.
Farm- Rodenberg No. 1

SEC. 17 T. 17 R. 31W
C SE NW

Total Depth. 4614'
Comm. 12-11-64 Comp. 12-24-64
Shot or Treated.
Contractor. D. R. Lauck
Issued. 3-13-65

County Scott KANSAS



Elevation. 2929' GL
2955' KB

Production. Dry

CASING:

8 5/8" 285' cem w/175 sx.

Figures Indicate Bottom of Formations.

surface clay & sand streaks	120
sand	175
blue shale	285
shale	1580
shale & shells	1790
very hard Anhydrite, red bed & shale	1817
red bed & shells	2065
shale, shells & red bed	2295
Anhydrite	2313
Lime & shale	2487
shale & shells	2990
lime & shale	3083
shale & lime	3150
lime	3290
lime & shale	3350
lime	3448
shale & lime	3615
lime & shale	3755
broken lime	3870
lime	3940
lime & shale	4005
lime	4614
Total Depth	4614

TOPS: Sample Log

Heebner	3903
Toronto	3922
Lansing	3941
Base Kansas City	4322
Marmaton	4327
Cherokee shale	4495
Cherokee sand	4557
Mississippian	4576
TD.	4614

SCHLUMBERGER

3902
3921
3941
4315
4322
4495
4563
4578
4615

DST # 1 (W) 3970-4005, opn. 1hr.w/strong
blow. Rec. 1620' salt wtr.
ISIP 1133#/30min.FSIP 1111#/30 min. IFP 75#
FFP 766#

DST # 2 (W) 4033-4059, opn 1 hr.w/weak blow thruout. Rec.
210' watery mud. Isip 1133#/30min.FSIP 1004#/30 min.
IFP 21#, FFP 97#