

18-17-31W ✓


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- D.R. LAUCK OIL CO., INC.  
Farm- Brookover No. 2

SEC. 18 T. 17 R. 31W  
C SE SE

Total Depth. 4632'  
Comm. 4-21-65 Comp. 5-3-65  
Shot or Treated.  
Contractor. Co; Tools.  
Issued. 7-31-65

County Scott  
KANSAS



Elevation. 2957' D. F.

CASING:  
8 5/8" 283' w/190 sx cem.

Production. DRY

Figures Indicate Bottom of Formations.

surface clay	65
sand	215
shale	283
shale	1800
shale, anhydrite	1845
shale	2130
shale, shells	2320
Anhydrite	2338
shale	2400
shale, lime	3010
shale, lime shells	3210
lime	3225
lime, shale	3495
shale, lime, some chalky	3660
lime, shale	3780
lime	3875
shale, lime	3980
lime	4632
Rotary Total Depth	

TOPS:	SAMPLE SCHL.	
* Anhydrite scout	2320	
Heebner	3928	3928
Toronto	3948	3945
Lansing	3968	3966
B/Kansas City	4359	4356
Marmaton lime	4370	4368
Cherokee	4542	4540
Penn. sand	4608	4606
Mississippian	4626	4624

DST #1 (H) 400-40, op. 1 hr. w/strong  
blow 1 hr. Rec. 2400' water, 50' mud.  
ISIP 1129#/30 min. FSIP 1121#/30 min.  
IFP 977#. FFP 1099#.

DST #2 (H) 4055-70, op. 1 hr. w/weak  
blow 30 min. Rec. 10' mud. ISIP 840#/30  
min. FSIP 795#/30 min. IFP 15#. FFP 46#.

DST #3 (H) 4215-40, op. 1 hr. w/strong  
blow 1 hr. Rec. 60' mud, 1520' water.  
ISIP 1129#/30 min. FSIP 1129#/30 min.