

BLOOMER

Form 113 50M 10-48-45767-D

State Kansas County EllsworthSec. 31 Twp. 17 Rng. 10W Elev. 1807Company Atlantic Refg.Well No. 2 Name Gemienhardt "B"Location SW SW SW (twin)Feet from lines: N. S. E. W. Spud 2-5-49 Completed 5-1-49T. D. 3244 Casing 5" 3242

PB 3070

Comp. Perf. 81' 2993-3055Pay 2993-3055 in Lans.I. P. 49 BOPD / 50% wtr.Choke T. P. C. P. G. O. R. Grvty.

DATE	REMARKS
5-1-49	Brn. ln. 2951, Lans. 2963, Arb. 3241, DST 2993-99, open 2 hr., rec. 6'
DWLE	mud, gd. por., stn., & oil 3050
	-- 79, DST 3051-82, open 35

DATE	REMARKS
	min., rec. 330' OCM, SO & wtr.
	SO 3136-40, 3146-50
	DST 3137-52, open 1 hr., rec. 12' OCM & 30' M & W.
	RTD 3244, gd. por. & sat. Ran Schlum.
	CO 3215, 36 § 3146-50 NS, 36 § 3135-40, B/10 CO + 8 GMPH, 1000 A, Swb/4 BO + 17 BW/8, PB 3070, 45 § 3050-55, SO, 1000 A, Swb/1 BO + 10 DMPH, 36 § 2993-99, wtr. set pkr 3025, 6000 A, Swb/60 BO + 20 BW/6, P/L9 BOPD + 50% wtr.
	COMPLETE
	E 09989