

IMPORTANT
Kans. Geo. Survey request
samples on this well.

15-203-20035

WICHITA DRILLING
KANSAS DRILLERS LOG

CONFIDENTIAL

S. 36 T. 17S R. 37W E
W
Loc. 1405' FSL & 2490' FWL
County Wichita

API No. 15 _____
County _____ Number _____

Operator
Stoltz, Wagner & Brown

Address
Box 1714 Midland, Texas 79701


Well No. #1 Lease Name LINDBERG

Footage Location
1405 feet from XX (S) line 2490 feet from (X) (W) line

Principal Contractor Service Drilling Co. Geologist _____

Spud Date 4/9/76 Total Depth 3130' P.B.T.D. _____

Date Completed 5/8/76 Oil Purchaser NA



Locate well correctly
Elev.: Gr. 3316'
DF _____ KB _____

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12-1/4	8-5/8	20#	341	Reg.	250	3%CC
Production	7-7/8	5-1/2	9-1/2#	3130	50/50 pox	180	2%gel, 3% salt

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			12	3/8" DP	2752-2758
TUBING RECORD			12	3/8" DP	2712-2718
			16 shots		2782-90
Size	Setting depth	Packer set at			
		NA			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Fraced w/20,000 gals gel water w/1# of 10/40sand/gal	2712-2758
Acidized w/1000 gals 15% HCL	

INITIAL PRODUCTION

Date of first production _____ Producing method (flowing, pumping, gas litt, etc.) _____

RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio
	bbls.	MCF	bbls.	CFPB
Disposition of gas (vented, used on lease or sold)			Producing interval (s)	

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator STOLTZ, WAGNER & BROWN		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:
Well No. 1	Lease Name LINDBERG	
S. 36 T. 17S. R. 27W ^E _W		

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Chase Winfield Council Grove	2710 2778 2964		Gamma Ray Correlation Log & Cmt. Bond Log	

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	_____ Signature
	_____ Title
	_____ Date