


35-17-4W



NOV 22 1969

Blackstone Drilling, Inc.

Box 455 • 523 West Kansas • Phone CH 1-1250

McPHERSON • KANSAS

67460

October 15, 1969

COMPANY: HUMMON OIL INCORPORATED
 CONTRACTOR: BLACKSTONE DRILLING, INC.
 FARM: S. JOHNSON #1
 LOCATION: C-5/2 SW/4 SE/4 35-17-4
 McPherson County, Kansas
 COMMENCED: October 7, 1969
 COMPLETED: October 14, 1969
 ELEVATION:

35-17-4W
C5/2 SW SE

#1 S. Johnson

Dry

0	to	20	Shale
20	to	40	Sand
40	to	75	Shale
75	to	135	Blue Shale
135	to	410	Shale & Lino
410	to	615	Lino
615	to	915	Lino & Shale
915	to	1650	Shale & Lino
1650	to	1885	Lino & Shale
1885	to	2035	Lino
2035	to	2350	Lino & Shale
2350	to	2350	Lansing
2350	to	2765	Lino
2765	to	2986	Shale & Lino
2986	to	3249	Mississippi
3249	to	3435	Shale
3435	to	3550	Shale & Lino
3550	to	3555	Lino
		3555	T. B.

Cut 17 in. hole to 135 ft. and run 137 ft. of 1 1/2 in. surface pipe, cemented with 125 sacks of cement with 3 percent calcium chloride, plug down at 3:30 P. M. on October 7, 1969. Cut 12 1/4 in. hole to 410 ft. and run 420 ft. of 3 5/8 in. surface pipe, cemented with 150 sacks of cement with 4 sacks Bull's, 3 percent Cel and 3 percent of calcium chloride and 100 sacks of cement with 3 percent calcium chloride. Plug down at 2:15 P. M. on October 8, 1969. Drilled 3 5/8 in. hole to 3553 ft. Layed down drill pipe, filled hole to 225 ft., Set plug with 25 sacks of cement. Filled with mud to 40 ft., set plug at 40 ft. and filled with 10 sacks of cement and 2 sacks in the rothole. Plugging completed at 10:00 P. M., October 14, 1969. Plugging completed by Hugh Scott, State Plugger, McPherson, Kansas.

TOPS: LANSING - 2350' Mississippi - 2986' Kinderhook - 3435' Viola-

Measurements taken from K. B.