

Operator
Dorchester Exploration, Inc.

DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWDW, ETC.:
Dry hole

Well No. 1 Lease Name
Wear

S 31 T 19 R 40 ~~SE~~
W

WELL LOG


Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
<p>D.S.T. #1 2940 to 2970 feet Prewflow 15 minutes, weak blow Open 60 minutes, no blow Recovered: 5 feet drilling mud</p> <p>Initial Hydrostatic Pressure - 1682 lbs. Initial Prewflow Pressure - 37 lbs. Final Prewflow Pressure - 37 lbs. Initial shut-in pressure -(30 Min.)62 lbs. Initial flow pressure - 37 lbs. Final flow pressure - 37 lbs. Final shut-in pressure-(60 Min.)62 lbs. Final hydrostatic pressure-1670 lbs.</p> <p>DST #2 2980 to 3006 feet</p> <p>Prewflow 15 minutes, weak blow Open 60 minutes, weak blow Recovered: 150 feet saltwater</p> <p>Initial hydrostatic pressure - 1707 lbs. Initial preflow pressure - 25 lbs. Final preflow pressure - 62 lbs. Initial shut-in pressure-(30 Min.)564 lbs. Initial flow pressure - 62 lbs. Final flow pressure - 87 lbs. Final shut-in pressure-(60 Min.)451 lbs. Final hydrostatic pressure - 1695 lbs.</p>			<p>Base Stone Corral</p> <p>Upper Winfield Lower Winfield Upper Ft.Riley</p> <p>Logs: Welex Gamma Guard 350</p> <p>Compensated Acoustic Velocity 1500</p>	<p>2618</p> <p>2907 2948 2977</p> <p>3006</p> <p>3006</p>

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received



[Signature]
Signature
Vice President
Title
March 1, 1974
Date

2E411E

ELECTRICAL LOG RELEASE FORM

23-17-40W

KANSAS GEOLOGICAL SOCIETY

KANSAS GEOLOGICAL BUILDING
P. O. BOX 843 / TELEPHONE 239-5877
WICHITA, KANSAS 67201

The undersigned, being duly authorized, hereby permits the release of the following electrical well log to the Kansas Geological Society for reproduction and distribution to its clients.

Company Dorchester Exploration, Inc. Sec. 23 Twp. 17S Rge. 40W

Farm Wear No. 1 Location C SE

WILL YOU CHECK BELOW, NAME OF THIS SURVEY.

ELECTRA GREAT GUNS SCHLUMBERGER WELEX County Greeley

Date Surveyed 12-14-72 State Kansas

IF THIS IS A SCHLUMBERGER OR LANE WELLS, PLEASE SEND COPY AS THEY NO LONGER MAINTAIN A FILE OF EXTRA LOGS.

PLEASE SIGN

OPERATOR Dorchester Exploration, Inc.

By [Signature]

J. D. Cooper

Date March 1, 1974

Remarks:

Please Indicate:

Will Mail

Should we call at your office for copies

Should we obtain copies from Surveying Co. EXCEPT SCHLUMBERGER AND LANE WELLS

We can use either the original negative or paper copy.

MAY WE KEEP THIS COPY FOR THE K.G.S. LIBRARY

YES NO

