


State Geological Survey  
**KANSAS DRILLERS LOG**  
 WICHITA, KANSAS

**IMPORTANT**  
 Kans. Geo. Survey request  
 samples on this well.

API No. 15 — 071 — 20,088  
 County Number

S. 29 T. 17 R. 40<sup>E</sup><sub>W</sub>  
 Loc. C NW  
 County Greeley

640 Acres  
 N



Elev.: Gr. 3628  
 DF KB 3633

Operator  
 Banks & Rhodes

Address  
 Box 242 Midland, Texas

Well No. #1 Lease Name Roe

Footage Location  
 1320 feet from (N) line 1320 feet from (E) (W) line

Principal Contractor D N B Drilling, Inc. Geologist D. Lloyd Henderson

Spud Date 9-2-75 Total Depth 3025 P.B.T.D. -

Date Completed 9-5-75 Oil Purchaser Sunflower Coop.

**CASING RECORD**

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12-1/4"	8-5/8"	20#	250	Common	175	3% Ca Cl.
Production	7-7/8"	4-1/2"	10.5#	3019	Class H Pozmix	400 150	1/4# flocele/sk 6# salt/sk

**LINER RECORD**

**PERFORATION RECORD**

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
TUBING RECORD			9 shots total	2937-68'	
Size 2-3/8"	Setting depth 2965	Packer set at -			

**ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD**

Amount and kind of material used	Depth interval treated
Acidized w/1000 gals. 15%	all holes
Frac w/19,000 gal. 2% gelled KCL water & 14,500# 10/20 sand	all holes

**INITIAL PRODUCTION**

Date of first production shut in Producing method (flowing, pumping, gas lift, etc.) flowing

RATE OF PRODUCTION PER 24 HOURS  
 Oil -0- bbls. Gas 2279 MCF Water -0- bbls. Gas-oil ratio gas CFPB

Disposition of gas (vented, used on lease or sold) shut in Producing interval (s) 2937-68'

**INSTRUCTIONS:** As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Banks & Rhodes

DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:

Well No. 1

Lease Name Roe

Gas

S 29 T 17 R 40 W


WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
No DST's				
No Cores			Welex Gamma- Acoustic Velocity	250'-3022'
<u>Lower Winfield</u> , tan to buff, very fine grained dolomitic sandstone, porous friable in part, contains gas.	2923	2958		
<u>Upper Fort Riley</u> , dolomitic sandstone, as above, contains gas.	2970	2991		
			Formation Tops	
			Base Stone Corral	2614
			Upper Winfield	2915
			Lower Winfield	2923
			Upper Ft. Riley	2970
			Lower Ft. Riley	3020

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.



\_\_\_\_\_  
*R. C. Banks*  
 Signature  
 \_\_\_\_\_  
 Operator  
 \_\_\_\_\_  
 Title  
 10-15-75  
 \_\_\_\_\_  
 Date

311438

State Geological Survey  
WICHITA, BRANCH

DRILLERS' LOG

29-17-40W

BANKS & RHODES  
No. 1 Roe  
C NW/4, Sec. 29-17S-40W  
Greeley County, Kansas

Elev: 3634 K.B. (Est.)

Commenced: 9-2-75  
Completed: 9-5-75

Surface: 242' of 8-5/8"  
cemented w/175 sx common  
cement, 3 1/2 cc. 9-2-75

FORMATION

DEPTH

Surface Hole	0 - 250
Shale	250 - 1605
Lime & Shale	1605 - 2020
Shale & Lime	2020 - 2287
Anhydrite	2287 - 2334
Lime & Shale	2334 - 2975
Shale & Lime	2975 - 3025 RTD

I do hereby certify that the foregoing statements are true and correct to the best of my knowledge and belief.

D N B DRILLING, INC.

*James L. Donelson*  
JAMES L. DONELSON

STATE OF KANSAS: ss:

Subscribed and sworn to before me this 17th day of September, 1975.

*Ella Priess*

Ella Priess, Notary Public

