

15-071-20158

IMPORTANT
Kans. Geo. Survey request
samples on this well.

Geological Survey
WICHITA BRANCH
KANSAS DRILLERS LOG

API No. 15 — 071 — 20,158
County Number

S. 31 T. 17 R. 40 ^W
Loc. 990' FNL & 990' FEL NE
County Greeley

Operator
R. C. Banks

Address **Box 242 Midland, Texas 79701**


Well No. #1 Lease Name **Smith Company**

Footage Location
990 feet from (N) (X) line 990 feet from (E) (W) line

Principal Contractor **Lakin Drilling Co.** Geologist **Lloyd Henderson**

Spud Date **9-8-78** Total Depth **3020'** P.B.T.D. **3020'**

Date Completed **9-16-78** Oil Purchaser



Elev.: Gr. **3635'**
DF _____ KB **3642'**

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
surface	12 1/4"	8 5/8"	23#	249'	Class H	275	1/4 Flocele 3% CaCl
production	7 7/8"	4 1/2"	9.50#	3047'	50/50 Poz	125	18% salt 3/4 of 1% CFR2

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			2		2960-2964
TUBING RECORD			2		2956-2960
Size	Setting depth	Packer set at			
2 3/8	2970	none			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Acidized 500 gal. 15%	2960-2964
Acidized 500 gal. 15%	2956-2960
No gas shows - plugged 5-17-79	

Form CP-1 filed 5-14-79 INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.)			
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio	
	bbls.	MCF	bbls.	CFPB	
Disposition of gas (vented, used on lease or sold)			Producing interval(s)		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator **R. C. Banks** DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:

Well No. **1** Lease Name **Smith** **Dry Hole**

S 31 T 17 R 41 ^X W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Base Stone Corral	2630'			
Winfield Formation	2928	2936		
Towanda	2938	2980		
Upper Ft. Riley	2980	3017		
Top Lower Ft. Riley	3027			
Perf. 2960-64 (Towanda) tested formation, rec. water w/slight show gas. Plugged & Abandoned				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	<div style="border-bottom: 1px solid black; margin-bottom: 5px; text-align: right;">Signature</div> <div style="border-bottom: 1px solid black; margin-bottom: 5px; text-align: right;">Title</div> <div style="border-bottom: 1px solid black; text-align: right;">Date</div>
---------------	--

QH1112