

State Geological Survey
KANSAS DRILLERS LOG
WICHITA, KANSAS

IMPORTANT
Kans. Geo. Survey request
samples on this well.

S. 35 T. 17 R. 40 ^W
Loc. 330' FSL & 1980' FEL
County Greeley

API No. 15 — 071 — 20,104
County Number

Operator
Argonaut Energy Corp.

Address
Box 12099 Amarillo, Texas 79101


Well No. # 1 Lease Name H. W. Gibson

Footage Location
330' feet from XX (S) line & 1980' feet from (E) XX line

Principal Contractor Service Drilling Co. Geologist

Spud Date 2/25/76 Total Depth 3000 P.B.T.D. 2963

Date Completed 3/5/76 Oil Purchaser None



Elev.: Gr. 3563'
DF _____ KB _____

CASING RECORD

Report of oil strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8 5/8"	23 & 24#	1281'	Pozmix	550	6% gel 2% C.C.
						200	Class H 3% C.C.
Intermediate	7 7/8"	4 1/2"	11.6#	3,006'	"	200	2% Gel, 18% salt saturated

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
NONE			2	3 1/8"	2915-19'
				Omega	2922-32'
				0.40" Jet	2936-42'

TUBING RECORD

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
1500 gal 7 1/2% Hcl acid & 30 ball sealers	2915-2942'
20,000 gal. 3% gelled acid & 18,000# 20/40 sand	2915-2942'

INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.)			
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio	
	bbls.	MCF	bbls.	CFPB	
Disposition of gas (vented, used on lease or sold)			Producing interval(s)		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator ARGONAUT ENERGY CORPORATION DESIGNATE TYPE OF COMP.: OIL, GAS, DRY-HOLE, SWDW, ETC.: Gas

Well No. 1 Lease Name GIBSON, H. W.

S 35 T 17 S R 40 W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
	0	40		
Sand, Shale, Red Bed	40	860		
Sand, Shale, Anhydrite	860	1156		
Shale, Anhydrite	1156	1250		
" "	1250	1320		
Shale	1320	1890		
" , Anhydrite	1890	2750		
" "	2750	3000	Towanda	2922-48'
		UCCL		

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

Robert L. Patterson
 Robert L. Patterson Signature
 Vice President of Production Title
 April 14, 1976 Date

97711E