

CONTINENTAL OIL CO.
R. Jansen No. 2

SEC 22 T. 17 R. 8W.
CWL SW
1320' N 440' E SW cor.

Total Depth. 3239
Comm. 4-5-40 Comp. 4-20-40
Shot or Treated. No acid
Contractor.
Issued. 7-6-40

County Ellsworth.



CASING.

10 3/4" 195'
7" 3232'

Elevation.

Production. Pot. 1062 B.
no wtr.

Figures Indicate Bottom of Formations.

surface	194
shale blue	375
rod bed & shalo	680
shalo and sholls	855
salt	1060
shale and sholls	1170
lime and sand	1335
brokon lime	1470
sand	1485
brokon lime	1590
shalo and sholls	2335
brokon lime	2415
shalo and sholls	2470
lime	2725
shalo and sholls	2823
lime	3135
lime and shalo	3197
shalo and sand	3229
shalo	3244
3244 equals 34 corr.	
Arbuckle lime	3239
Total Depth.	

Top of Arbuckle lime from
cement floor level 3230

Drilled cement plug and hole filled up 800' with oil in 1 hour.
Total Fillup 3060'

4-24-40 On initial potential test well pumped 353.88 bbls oil in
8 hours giving the well a 24 hour potential of 1062 bbls of oil no
water, no Acid.

Total Depth from cement floor level 3239.