

21-17-8W


WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY  
412 Union National Bk. Bldg., Wichita, Kansas

Company NELSON DRILG. CO.  
Farm Jansen No. 3

SEC. 21 T. 17 R. 8 W  
CS/2 SE NE

Total Depth. 3233'  
Comm. 4-21-46 Comp. 5-9-46  
Shot or Treated. 2000 gals. & 2000 gals. acid.  
Contractor. Nelson Drilg. Co.  
Issued. 5-25-46

County. Ellsworth  
KANSAS



Elevation. 1791

CASING:  
10" 171' Cem.  
7" 3190' Cem.

Production. Pot. 805 B.

Figures Indicate Bottom of Formations.

surface	0-171
sand-shale & shells	515
shale, salt & shells	1040
shale & shells	1120
anhydrite	1195
lime & shale	1435
shale & shells	1480
sand	1510
lime brkn	1700
shale & lime	1735
lime	1825
lime & shale	2430
lime	2760
lime & shale	2850
lime	3185
shale	3186
lime	3190
T.D. w/rotary	
Arbuckle -no show of	
oil	3192
Arbuckle-show of	
oil	3198
Arbuckle-more oil	
200' oil in 8	
hrs.	3204
Arbuckle - no show	3209
Arbuckle-more oil	3218
shale break-Arb.	3224
Arbuckle hrd	3227
Arbuckle & shale	
blue	3233
Total Depth.	

Acidized w/2000 gals. &  
reacidized w/2000 gals.  
acid.

Top of Arbuckle 3186'