


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas

CONTINENTAL OIL CO.
G. L. Baker No. 3.

SEC. 21 T. 17 R. 8W
CEL SE
1320' N 440' W SE Cor.

Total Depth. 3265'
Comm. 7-6-40 Comp. 7-22-40
Shot or Treated.
Contractor.
Issued. 9-28-40

County. Ellsworth



CASING:
10 $\frac{3}{4}$ " 199'
7 " 3261'

Elevation.

Production. Pot. 640 B.
No wtr

Figures Indicate Bottom of Formations.

shale	40
shale & shells	680
shale & shells	870
salt	1060
shale & shells	1265
shale & shells	1466
lime sdy	1489
lime brkn	1640
shale & shells	1835
shale & shells	2160
shale & shells	2420
lime	2650
lime	2780
shale & lime	2880
lime	3090
lime	3215
sand	3225
shale	3263
Arbuckle lime	3265
Total Depth.	

Top of Arbuckle lime from
cement floor level 3259
Total fillup w/oil 2800'
7-25-40 acidized w/1000 Gals.
7-26-40 on a 4-hr pumping test
the well pumped 123 BO, no
wtr
7-27-40 on initial potential
test the well pumped 213.21
BO in 8 hrs, giving the well
a 24-hr potential of 640 BO,
no wtr
Total depth from cement floor
level 3264