

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas

CONTINENTAL OIL CO.
F.M. Grey No. 1


SEC. 26 T. 17 R. 8W
SW SE SE
330' N and 990' W of SE cor.

Total Depth. 3310 P.B. 3205
Comm. 9-25-38 Comp. 10-10-38
Shot or Treated.
Contractor.
Issued. 12-24-38

County Ellsworth.

CASING.

13" 284'



Elevation. 1722

Production. DRY.

Figures Indicate Bottom of Formations.

cellar	8	red conglomerate	3267
surface clay	20	sand no show	3280
lime	45	shale	3291
shale and sand	180	sand and lime	3310
shale and lime shells	290		
red bed	305	Total Depth.	
broken lime	375		
shale and lime shells	445	Top Kansas City	2790
shale	456	Top Viola lime	3190
red bed and shale	496	Top Arbuckle lime	3295
broken anhydrite	514		
shale and shells	850	Cored 3300' - 3310 with a 4'	
salt	1025	Rec. of Arbuckle lime, spotted	
shale and lime broken	1040	with spots of dead oil.	
lime	1070		
broken lime	1120	10-11-38 Halliburton drill stem	
shale and shells	1179	test 122' of muddy water with a	
shale and lime	1246	very slight trace of oil.	
shale and lime shells	1420		
sand	1432	10-11-38 Schlumberger Test	
broken lime	1448		
shale and shells	1537	Tops as follows -	
lime and shale	1619		
broken lime	1660	Top Topoka lime	2405
broken lime and shale	1690	Top Kansas City lime	2787
broken lime	1720	Main body of K.O. lime	2800
shale and lime	1750	Possible show of oil and gas	
broken lime	1756	at 2775-2790	
broken lime and shale	1831	Sdy shale slight porosity	2790-2800
broken lime	1864	Very small sh, very small porosity	2810-2820
shale and shells	1931	small show oil, very small porosity	2915-2930
shale and lime broken	1980	Water	3105-3120
shale and shells	2055	Dolomitic lime, possible oil and gas	3130-40
shale and lime shells	2167	water	3145-3165
broken lime	2209	Top Viola lime	3165
shale and shells	2252	show oil and gas	3167-3192
shale and lime broken	2323	Top Arbuckle lime	3295
shale and shells	2403	water	3295-3307
lime	2490	P.B. from 3310- to 3205.	
broken lime & shale	2580		
lime	2616	Took Halliburton Drill stem test from 3190	
broken lime	2700	to 3215 setting the packer at 3190. opened	
broken lime and shale	2743	for thirty min. The test showed 80' of	
broken lime	2806	muddy water. no oil or gas.	
lime soft porous	2819		
lime and shale	2825	11-15-38. The hole was filled with heavy mud	
shale and lime broken	2884	from 3215- to 290	
broken lime	2916		
lime	2947		
lime and shale	2953		
lime	3158		
shale brown	3192		
lime	3246		
dolomite	3257		