


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.  
412 Union National Bk Bldg., Wichita, Kansas.

CONTINENTAL OIL CO.  
W. Ploog No. 2-A.

SEC. 27 T. 17 R. 8W  
NE SE SW SW  
440' N 1312' E SWc

Total Depth. 3254'  
Comm. 2-11-38 Comp. 3-6-38  
Shot or Treated. 2000 Gals.  
Contractor.  
Issued. 5-28-38

County. Ellsworth



Elevation. 1775'

CASING:  
10<sup>3</sup>/<sub>4</sub>" 228'  
7 " 3245'

Production. Pot. 1668 B.  
No wtr.

Figures Indicate Bottom of Formations.

surface sand	230
shale & red bed	363
red bed & gyp shells	701
shale	1055
shale & lime	1405
salt & shells	1527
shale & lime	1901
shale & shells	2211
brkn lime	2301
shale & lime	2426
lime & brkn lime	2910
lime & salt	2920
lime & brkn lime	3208
conglomerate	<b>3233</b>
shale Top Siliceous 3244	3246
Siliceous lime	3254
Total Depth.	

3244  
1775  
-----  
1469

Pumped 296 B. 1st 4 hrs.  
Pumped 277 B. 2nd 4 hrs.  
Pumped 1668 B. 24 H. Pot. No wtr.