


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bk Bldg., Wichita, Kansas.

CONTINENTAL OIL CO.
Walter Steinberg No. 2.

SEC. 27 T. 17 R. 8 W
CSL N/2 NW

Total Depth, 3247'
Comm. 5-3-38 Comp. 5-26-38
Shot or Treated.
Contractor.
Issued. 7-23-38 Rotary O-3216
Cable 3216-3247

County. Ellsworth



CASING:
10³/₄" 207'
7 " 3215'

Elevation.

Production. Pot. 2473 B.
No wtr.

Figures Indicate Bottom of Formations.

surface sand	207
blue shale & lime shls	330
red bed	534
shale & shells	790
shale & red bed	1100
anhydrite & salt	1235
shale & salt	1511
shale, lime & salt	1600
shale & shells	2004
shale	2100
shale & lime	2225
shale	2246
lime	2780
shale & lime shells	2806
lime	3198
shale	3214
Siliceous lime	3247
Total Depth.	

The cement plug was drilled to bottom (3216') and the hole filled up with oil at the rate of 1900' per hour, after drilling to 3232' the hole was full of oil.

On a six hour pumping test the well pumped 514.56 bbls oil.

On state initial potential test the well pumped 412.16 bbls oil the 1st 4 hrs and 413.36 bbls oil the last four hrs giving the well a 24-hr potential of 2473 bbls oil, no wtr.

Siliceous lime 3214-3247