


CONTINENTAL OIL CO.
Walter Steinberg No. 5

SEC. 27 T. 17 R. 8W.
CWL NW $\frac{1}{4}$
1320' North and 440' East of
W/4 Corner.

Total Depth. 3236
Comm. 8-27-40 Comp. 9-16-40
Shot or Treated.
Contractor.
Issued. 11-30-40

County Ellsworth.



CASING.

103/4" 209' cemented.
7" 3203' cemented.

Elevation.

Production. Pot. 299 B.
No wtr.

Figures Indicate Bottom of Formations.

surface	40
shale and shells	730
shale	860
salt	1060
shale and shells	1380
broken lime	1435
shale and shells	1450
sdv lime	1475
lime	1545
shale and shells	2085
shale and lime	2270
shale and shells	2405
shale and shells	2420
lime	2715
shale and shells	2720
shale and lime	2810
lime	3157
shale	3160
lime and shale	3190
shale	3200
lime	3236

Total Depth. from cement floor level.

Top of Arbuckle lime from cement floor level 3203
9-14-40 acidized w/1000 Gals. Acid
Total fillup w/oil 1700'

9-18-40 Acidized with 3000 gal.

9-20-40 On intial potential test, the well pumped
99.63 bbls of oil in 8 hours giving the well
a 24 hour potential test of 299 bbls oil and
no water.