


WELL LOG BUREAU * KANSAS GEOLOGICAL SOCIETY.
412 Union National Bk Bldg, Wichita, Kansas.

CONTINENTAL OIL CO.
O.O. Fuller No. 2

SEC. 28 T. 17 R. 8W.
CSL SE $\frac{1}{4}$
440' N 1320' W of Sec

Total Depth. 3233.
Comm. 2-3-39 Comp. 3-1-39
Shot or Treated. 2000 gal.
Contractor. Parker Drilling Co.
Issued. 4-29-39

County Ellsworth.



CASING.

1 $\frac{3}{4}$ " 221
7" 3182

Elevation.

Figures Indicate Bottom of Formations.

Production Pot. 2222.07
oil and no water.

collar	9-6
surface soil	28
sand rock	60
shale and shells	140
shale and sand rock	205
shale and shells	320
red bed	375
anhydrite	390
red bed shells and shale	600
red bed and shale	680
shale and shells	908
salt and shale	1070
shale and shells	1165
shale and lime	1285
shale and shells	1449
sa d	1471
shale and shells	1530
sand and shale	1539
shale and shells	1572
shale and lime shells	1875
shale and shells	2100
broken lime	2123
shale and lime shells	2275
shale	2309
broken lime	2360
broken lime & shale	2423
lime	2460
lime broken	2493
lime	2674
lime and pyrite	2688
lime	2733
shale and red bed	2760
chert lime	2802
lime	2847
lime	2978
shale and lime	2994
lime	3048
lime	3118

lime and shale	3159
shale	3166
lime	3167
shale	3178
Simpson sand	3182
Arb. Dolomite	3184
lime	3218
shale	3221
lime	3233
Total Depth.	

Top of Arbuckle 3181

Total fill up with oil 3050

3-6-39 acidized with 2000 gal. acid.

On initial Potential test the well pumped 740.69 bbls of oil in eight hours giving the well a 24 hours pot of 2222.07 bbls of oil no water.