


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas

CONTINENTAL OIL CO.
O.O. Fuller No. 4.

SEC. 28 T.17 R.8W
NEc SE
440'S 440'W E $\frac{1}{4}$ Cor.

Total Depth. 3226'
Comm. 5-23-40 Comp. 6-8-40
Shot or Treated. 6-11-40 2000 Gals. Acid
Contractor.
Issued. 8-17-40

County. Ellsworth



CASING:

10 $\frac{3}{4}$ " 208'
7" 3183'

Elevation.

Production. Pot. 5377 B. Echo.

Figures Indicate Bottom of Formations. No wtr, Max. Pot. 3000 B.

clay & sand	211
shale brkn	325
shale & red bed	460
shale	860
salt	1060
shale & shells	1400
lime	1435
sand	1470
lime	1495
shale & shells	1660
lime	1755
shale & shells	1980
shale	2100
lime	2115
shale	2175
shale & shells	2385
shale	2500
lime	2710
shale	2800
lime	2850
break	2867
lime	2940
break	2957
lime	3196
shale & lime	3215
lime	3226
Total Depth.	

Top of Arbuckle lime from
cement floor level 3181
Total depth from cement floor
level 3225
Total fillup w/oil 3100
6-11-40 acidized w/2000 Gals.
6-13-40 obtained an Echo Meter
potential test of 5377 bbls
oil, no wtr. This potential
establishes a maximum allowed
potential of 3000 bbls.