


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas

CONTINENTAL OIL CO.
H.A.Kunkle "B" No. 1.

SEC.28 T.17 R.8 W
SEc SW
330'N 330'W S $\frac{1}{4}$ Cor.

Total Depth. 3239' (CF 3238)
Comm. 5-12-42 Comp. 5-30-42
Shot or Treated.
Contractor.
Issued. 8-8-42

County. Ellsworth



CASING:
10 $\frac{3}{4}$ " 201' Cem.
6" 3229' Cem.

Elevation.

Production. Echo.Pot.1843 B.
No wtr
Figures Indicate Bottom of Formations.

shale & shells	206
shale & shells	730
shale & shells	1010
shale & shells	1315
shale & shells	1470
sand	1500
lime brkn	1530
lime brkn	1725
shale & shells	1880
shale & shells	2355
shale & lime	2460
lime	2610
lime	2670
lime & shale	2860
lime	3015
lime	3130
lime	3231
Arbuckle	3235
lime	3239

Total Depth.

Total Depth cement
floor 3238

Top Arbuckle lime 3228

350' oil in hole in 15 hrs
5-30-42 acidized w/500
gal.acid - swbd dry &
swbd 11 $\frac{1}{2}$ bbls oil in 30
min.off btm
total fillup w/oil 3000'
estb.a swbg temp.potential
of 77 bbls oil 6-1-42
6-17-42 acidized w/2000
Gals.acid
6-18-42 estb.Echo.Pot.
1843 BO, no wtr

Note: All of above foot-
ages are calculated from
the cement floor level.