


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas

CONTINENTAL OIL CO.
H.A.Kunkle No. 2.

SEC.28 T.17 R.8W
NW NE SE SW
1240'N 440'W S $\frac{1}{2}$ Cor.

Total Depth. 3247' (CFL 3246)
Comm. 8-31-41 Comp. 9-16-41
Shot or Treated.
Contractor.
Issued. 11-15-41

County. Ellsworth



CASING:
10 $\frac{3}{4}$ " 206' Cem.
6" 3243' Cem.

Elevation.

Production. Pot.148 B.Phy.
21 BW

Figures Indicate Bottom of Formations.

shale & shells	100
sand & shale	210
shale & shells	705
shale	860
salt	1050
shale & shells	1240
lime & shale	1370
lime brkn	1460
sand	1470
sand & lime	1580
lime & shale	1905
shale & shells	2390
shale	2445
lime	3085
lime & shale	3135
lime	3224
shale	3245
dolomite	3247
Total Depth.	

Total depth from cement
floor level 3246

Top of Arbuckle lime 3242
Total fillup w/oil 700' -
swbd 31 BO, no wtr
9-17-41 acidized w/2000
Gals.
9-18-41 established a 24-
hr physical potential of
148 BO, 21 BW

Note: all of above footages
are calculated from the
cement floor level.