


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.  
412 Union National Bank Bldg, Wichita, Kansas.

CONTINENTAL OIL CO.  
L.L.Rolf's No. 5

SEC. 28 T. 17 R. 8W.  
CEL NE  
1320' So. 440' W of NE Cor.

Total Depth. 3235  
Comm. 9-23-40 Comp. 10-11-40  
Shot or Treated.  
Contractor.  
Issued. 1-25-41

County Ellsworth.



CASING.

103/4" 203' cemented.  
8" 3191' cemented.

Elevation.

Production. Pot. 478 B.  
No wtr

Figures Indicate Bottom of Formations.

surface clay & shale	203
shale blue	355
red rock and shale	740
shale and shells	868
salt	1075
shale and shells	1105
broken lime	1180
shale and shells	1265
shale and lime	1456
sand	1478
broken lime	1485
broken lime	1710
shale and shells	2400
shale and lime	2495
lime	2750
shale and shells	2810
shale	2850
lime	3175
shale	3193
dolomite	3202
lime	3203
lime and shale	3205
lime	3235
Total Depth.	

Total Depth from cement floor level 3234  
Top of Arbuckle lime from cement floor level 3189  
Total fill up oil 2800'

10-14-40 Acidized with 2000 gal. Maximum pressure on casing 1100#  
on tubing 925 #. pressure equalized to 925#.

10-15-40 On Physical potential test the well pumped 159.47 bbls  
of oil in 8 hours, giving the well a 24 hour potential of  
478 bbls of oil, no water.