

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.  
412 Union National Bank Bldg, Wichita, Kansas.

CONTINENTAL OIL CO.  
L.L. Rolfs No. 6

SEC. 28 T. 17 R. 8W.  
NW SW NE  
1315'N 440' E of Center.

Total Depth. 3234 (3233 Cem. Floor level)  
Comm. 1-7-41 Comp. 1-24-41  
Shot or Treated.  
Contractor.  
Issued. 3-29-41

County Ellsworth.



CASING.

10 3/4" 214' cemented.  
6" 3208' cemented.

Elevation.

Production. Pot. 257.77B.

Figures Indicate Bottom of Formations. no water. Physical

sand and clay	100
shale and shells	920
salt	1110
shale and shells	1245
lime and shale	1400
lime shale and sand	1510
shale and shells	1610
broken lime	1850
lime and shale	1945
shale and shells	2350
lime	2798
shale	2825
shale and shells	2850
lime broken	2930
broken lime	3035
lime	3145
lime and shale	3221
lime	3234
Total Depth.	

Total Depth from cement floor level 3233

Top of Arbuckle lime from cement floor level 3206.

Total Fillup with oil 2300'

1-26-41 Acidized with 2000 gal acid.

1-27-41 on Physical Potential test the well pumped 82.59 bbls oil  
in 8 hours, giving the well a 24 hour potential of 257.77 bbls oil no water.