


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas

CONTINENTAL OIL CO.
L.L.Rolfs No. 7.

SEC.28 T.17 R.8W
CNL NE
1320' W 440' S of NE Cor.

County. Ellsworth

Total Depth. 3242' (CFL 3241')
Comm. 2-3-41 Comp. 2-20-41
Shot or Treated.
Contractor.
Issued. 5-31-41



CASING:
10 $\frac{3}{4}$ " 205' Cem.
6 " 3211' Cem.

Elevation.

Production. Pot.308 B.Phy.
No wtr

Figures Indicate Bottom of Formations.

surface soil & clay	50
shale & shells	207
shale & shells	635
shale, shells, salt	1100
shale & shells	1290
shale & shells	1445
shale, sand & lime	1535
shale & shells	1660
shale & shells	1820
shale & shells	1940
shale & shells	2210
shale & shells	2450
lime	2780
shale & shells	2830
lime	3195
lime	3242
Total Depth.	

Total depth from cement floor
level 3241

Top of Arbuckle lime 3210

Total fillup w/oil 1200'

2-20-41 acidized w/1000 Gals.
2-21-41 acidized w/3000 Gals.
2-22-41 on physical potential
test the well pmpd 102.70 BO
in 8 hrs, giving the well a
24-hr potential of 308 bbls
of oil, no wtr

Note: Above footages calculated
from cement floor level.