

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.

CONTINENTAL OIL CO.
Herman Buehler No. 1

SEC. 33 T. 17 R. 8W.
Sec SE

Total Depth. 3288'
Comm. 2-11-37 Comp. 3-10-37
Shot or Treated. 4000 gal acid.
Contractor.
Issued. 10-9-37

County. Ellsworth.

CASING.

13" 201'
7" 3273'
5 1/2" 3346'



Elevation.

Production. DRY.

Figures Indicate Bottom of Formations.

cellar 8
red rock 76
sand and gravel 105
shale and shells 360
broken lime & red rock 574
shale and shells 1050
broken lime 1205
lime and shale 1330
shale and shells 1350
broken lime 1445
lime and shale 1620
broken lime 1621
lime and shale 1901
shale and shells 2184
shale and lime 2220
shale and shells 2340
broken lime 2475
lime 2511
broken lime 2544
lime 2640
broken lime and shale 2685
lime 2765
shale 2835
lime 2860
shale 2880
broken lime 2893
sand 2900
lime 2905
lime and shale 2970
shale and broken lime 3054
broken lime 3075
shale 3085
lime 3185
shale 3193
broken lime 3233
shale 3237
sand 3247

chert and congl. 3260
congl and shalo 3271
siliceous lime 3274
lime 3288
Total Depth.

DEEPENING RECORD.

Comm. 6-19-37
Comp. - 8-15-37
Prod. Salt wtr Input well.
lime. 3288- 3680
sdy lime 3702
lime 3712
sdy lime 3723
red sand 3765
red rock 3770
red sand 3900
sand green 3907
red sand 3957
shale green 3962
red sand 3976
sand 3990
red sand 4217
sand - 4277
Total Depth.

8-6-37 well was acidized with 4000 gallons of acid.

8-7-37 water test. took 780 bbls water per hour.