


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bldg., Wichita, Kansas

CONTINENTAL OIL CO.
H. Buehler No. 3.

SEC. 33 T. 17 R. 8W
CEL NE
1320' S 440' W NE Cor.

County. Ellsworth

Total Depth. 3222'
Comm. 9-3-39 Comp. 9-20-39
Shot or Treated. 2000 Gals.
Contractor. Parker Drlg. Co.
Issued. 12-23-39



CASING:
10³/₄" 211'
6 " 3181'

Elevation.

Production Pot. 2001.03 B.

Figures Indicate Bottom of Formations, No water

cellar	9'4"
surface soil	28
sand	42
shale & sand rock	135
sand	165
sand rock	210
shale	379
lime	397
red bed, shale, shells	455
shale & shells	860
salt & shells	1050
shale, shells, lime	1095
brkn lime & shale	1220
shale & lime	1435
sand	1460
lime brkn	1515
shale & lime shells	1650
shale & shells	1795
shale & lime shells	1930
shale & shells	2445
lime	2475
lime brkn	2555
lime	2642
lime brkn	2711
shale & shells	2740
shale	2810
lime	2922
lime sft brkn	2934
lime	3104
lime brkn	3118
lime brkn & shale	3173
conglomerate	3182
lime Arbuckle	3189
lime	3222
Total Depth.	

T.D. from cement floor level 3221

Top of Arbuckle lime

from cement floor level 3179

Fillup w/oil 2500'

9-22-39 acidized w/2000 Gals.

9-23-39 on initial potential

test the well pumped 667.01

BO, 8hrs giving the well a

24-hr potential test of

2001.03 BO, no wtr.